# MyTiCon Timber Connectors

White Paper

# Inter-Story Drift Testing of KNAPP RICON S VS Connectors



# WOOD you like to CONNECT?

CONTACT US

Product Consulting 1.866.899.4090 info@my-ti-con.com

Technical Support 1.866.899.4090 upport@my-ti-con.com

www.my-ti-con.com

Discalaimer

# MyTiCon Timber Connectors

#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load

The information in this document is provided on an "as is" basis and for general information purposes only. While MTC Solutions aims to keep the information provided in this document complete, accurate, and in line with state-of-the-art design methods, MTC Solutions, its affiliates, employees, agents, or licensors do not make any representations or warranties of any kind, including, but not limited to, express or implied warranties of fitness for a particular purpose or regarding the content or information in this document, to the full extent permitted by applicable law.

The information in this document does not constitute engineering or other professional advice, and any reliance users place on such information is therefore strictly at their own risk. Images and drawings provided within this document are for reference only and may not apply to all possible conditions. MTC Solutions shall not be liable for any loss or damage of any kind, including indirect, direct, incidental, punitive, or consequential loss or damage arising out of, or in connection with, the information, content, materials referenced, or the use of any of the systems described in this document. Users may derive other applications which are beyond MTC Solutions' control. The inclusion of the systems or the implied use of this document for other applications is beyond the scope of MTC Solutions' responsibility.



#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load

The performance based design of tall wood buildings and their associated inter-story drift demands are an important design consideration. On the west coast of North America, tall wood buildings may be subject to dynamic loading scenarios throughout their service life. A typical post and beam glulam structure will, depending on the selection of the seismic force resisting system, experience story drifts which are typically limited to 2% by design codes. This story drift will also subject the respective post and beam connection to additional stresses. These stresses are a result of the gravity load and the rotation of the beams against the post. Since the connection will have to resist the gravity load while a major loading event such as an earthquake occurs, it is required to prove that the connection at major structural members can satisfy these demands. In order to provide respective data quasi-static rotational testing under the maximum design load of KNAPP RICON S VS connectors was conducted at the structures lab of the University of British Columbia.

A T-shape post to beam connection test setup (Figure 1) with a 9' long beam member and a 4' long post member was selected and subjected to a quasi-static reversed cyclic procedure. Two different D-Fir glulam cross sections were selected to receive the RICON S VS 200x60 and RICON S VS 200x80 connectors. A 6 3/4" x 13 1/2" D-Fir glulam received the small RICON S VS 200x60 connector to resist a factored design load of 9.6kips (42kN) and a 6 3/4" x 15" D-Fir glulam was selected to receive the larger RICON S VS 200x80 connector to resist a factored design load of 13.7kips (61kN). The required design load was constantly applied as a static shear load near the interface of post and beam. A second actuator applied a reversed cyclic (quasi-static) rotation at 65 1/4" distance to the interface was recorded. A total of 3 tests with each connector size were conducted. A summary of the findings is presented in this report.





Figure 1: General Test setup and typical RICON S VS connector

Report

MyTiCon Timber Connectors

Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load

#### Figure 2: General Test setup distances and measurements



Report





Figure 3: Displacement recording (#1) at interface of beam and column and constant design shear load application actuator (#2)




Figure 4: Displacement recording 73 1/2" away from interface of beam and post (near actuator applying rotation to beam)



Figure 5: Displacement application actuator (#3) at 65 1/4" away from interface of beam and post

Report

# Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load





Figure 6: Threaded rod tie to reaction frame at post member



Figure 7: Lateral bearing point at post to reaction frame




Figure 8: Reaction frame with specimen

#### Results

#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load

# MyTiCon Timber Connectors

#### Summary and conclusions

Three post to beam specimen of RICON S VS 200x60 and RICON S VS 200x80 under the specified design load has indicated that RICON connectors can resist static forces while subjected to a reversed cyclic rotational force. During testing two out of three RICON 200x60 connectors observed ultimate failure at the collar bolt through a combined tension and shear fracture of the bolt. Ultimate failure occurred after the 2.5° rotation and full actuator displacement in reversed cyclic fashion was applied. The actuator pushed the beam member 3" one directional and failure occurred before 3" of displacement was reached in the opposing cycle. A picture of the collar bolt failure is shown in Figure 15. Failure on the load bearing full thread ASSY VG CSK screws was not visually observed. An inter-story drift value of approximately 4% was calculated with the recorded string pot measurement divided by the distance of the string pot to the center of rotation (see Figure 2 for detailed measurements). The applied reinforcing screws perpendicular to the grain of the beam member avoided tension perpendicular to grain failure effectively and no failure was observed in the glulam members. The loading protocol was stopped after ultimate failure occurred or the maximum actuator stroke was reached (as reflected in the plots shown in this report).

During testing of the RICON S VS 200x80 connectors no ultimate failure was observed at the connectors, the ASSY VG CSK screws or the timber members. Intended damage on the connectors such as plastic yielding of the collar bolt, plastic deformation of the V-notch and early indication of perpendicular to grain splitting failure in the beam member was however noticed. The loading protocol was completed as desired after approximately 10 minutes of loading while the full actuator stroke was reached.

| Test    | Test connector<br>type | Max Gap*<br>[in] | Max Rotation**<br>+ [°] | Max Total Shear<br>[kip] | Max Moment***<br>[kip-in] | Max Static Design Shear<br>Resistance**** [kip] |
|---------|------------------------|------------------|-------------------------|--------------------------|---------------------------|---|
| Small-1 | 200x60-1               | 0.37             | 2.5                     | 10.8                     | 123.5                     |   |
| Small-2 | 200x60-2               | 0.43             | 2.5                     | 10.5                     | 124.4                     | 9.6   |
| Small-3 | 200x60-3               | 0.40             | 2.6                     | 10.5                     | 119.9                     |   |
|         | Average 200x60         | 0.40             | 2.5                     | 10.6                     | 122.6                     |   |
|         | COV 200x60 [%]         | 7%               | 1%                      | 2%                       | 2%                        |   |
| Large-1 | 200x80-1               | 0.43             | 2.5                     | 15.7                     | 169.8                     |   |
| Large-2 | 200x80-2               | 0.49             | 2.6                     | 13.7                     | 168.9                     | 13.7  |
| Large-3 | 200x80-3               | 0.42             | 2.5                     | 14.8                     | 162.4                     |   |
|         | Average 200x80         | 0.44             | 2.5                     | 14.7                     | 167.0                     |   |
|         | COV 200x80 [%]         | 9%               | 1%                      | 7%                       | 2%                        |   |

#### Table 1: Summary of test results

 $\Rightarrow$  \*The term "Gap" refers to the LDVT recording at the connection (see Figure 3)

 $\Rightarrow$  \*\*The beam rotation was calculated based on the distance of the string pot recoding and its distance to the center of the connection


 $\Rightarrow$  \*\*\*The Max moment is calculated as the sum of moments caused by the static force and dynamic force times the respective lever arm

 $\Rightarrow$  \*\*\*\*Refers to the factored resistance of the connector under standard term loading conditions

Results




#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load





Note: RICON S VS 200x60 collar bolt fracture observed in test and respective machine recordings




Note: RICON S VS 200x60 collar bolt fracture observed in test and respective machine recordings.


#### Results


# MyTiCon Timber Connectors

#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load



Note: RICON S VS 200x80 connectors without apparent connector failure







#### Results




#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load







Note: RICON S VS 200x60 collar bolt fracture observed in test and respective machine recordings with failure indication




#### Results












Results












## Results











#### Results




#### Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load







Note: RICON S VS 200x60 collar bolt fracture observed in test and respective machine recordings with failure indication
















Results




Figure 9: Example of collar bolt failure at maximum drift and load in beam member Ricon S VS 200x60 in 2 out of three tests. Figure 10: Example of collar bolt yielding at maximum drift and load in beam member RICON S VS 200x80 in 3 out of three tests

#### Results










During construction of a tall wood building wind suction may result in net uplift. To secure the assembly against uplift two toes screws were also installed into test specimen to simulate a full connection assembly (see Figure 12)


Results

# MyTiCon Timber Connectors



Inter-Story Drift Testing of KNAPP RICON S VS Under Design Load









screws

## Results








#### Results

# MyTiCon Timber Connectors











Find more resources for our modern timber connection systems, including technical design data, installation guides, CAD files, videos, research data and more white papers on our website

www.my-ti-con.com

Or

Contact us

info@my-ti-con.com

1-866.899.4090

**Technical Support** 

support@my-ti-con.com

1-866.899.4090